GeM Bid Document - SAMPLE FOR TESTING (made-up, not a real tender)
Bid Number: GEM/2026/B/5531902
Dated: 14-10-2026
Bid End Date/Time: 05-11-2026 15:00:00
Ministry/State Name: Rajasthan
Department Name: Public Works Department
Office Name: Executive Engineer, Electrical Division-II, Jaipur
Item Category: Supply, Installation, Testing and Commissioning of Internal Electrification and LT Distribution for Government Hospital Block
Estimated Bid Value: 48,60,000
Evaluation Method: Total value wise evaluation

Bid Details
Contract Period: 4 Month(s)
Minimum Average Annual Turnover of the bidder (For 3 Years): 60 Lakh(s)
Years of Past Experience Required for same/similar service: 3 Year(s)
MSE Exemption for Years Of Experience and Turnover: Yes
Startup Exemption for Years Of Experience and Turnover: No
Document required from seller: Experience Criteria, Bidder Turnover, Certificate (Requested in ATC), OEM Authorization Certificate, Additional Doc 1 (Requested in ATC)
Bid to RA enabled: Yes
Type of Bid: Two Packet Bid
Time allowed for Technical Clarifications during technical evaluation: 2 Days

EMD Detail
Advisory Bank: State Bank of India
EMD Amount: 97,200
ePBG Detail
ePBG Percentage(%): 5.00
Duration of ePBG required (Months): 16
Bidders seeking exemption from EMD: Micro and Small Enterprises (MSEs) registered with Udyam are exempted from submission of EMD, subject to uploading valid Udyam certificate with the bid.
The EMD of unsuccessful bidders shall be returned after award of contract.

General Terms and Conditions on GeM (continued)

1. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

2. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

3. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

4. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

5. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

6. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

7. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

8. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

9. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

General Terms and Conditions on GeM (continued)

10. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

11. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

12. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

13. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

14. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

15. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

16. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

17. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

18. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

19. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

20. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

21. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

22. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

23. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

24. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

25. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

26. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

27. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

28. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

29. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

30. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

31. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

32. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

33. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

34. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

35. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

36. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

37. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

38. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

39. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

40. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

41. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

42. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

43. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

44. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

45. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

46. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

47. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

48. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

49. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

50. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

51. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

52. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

53. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

54. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

55. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

56. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

57. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

58. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

59. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

60. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

61. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

62. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

63. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

Technical Specifications (continued)

1. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

2. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

3. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

4. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

5. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

6. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

7. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

8. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

9. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

10. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

11. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

12. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

13. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

14. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

15. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

16. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

17. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

18. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

19. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

20. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

21. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

22. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

23. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

24. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

25. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

26. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

27. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

28. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

29. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

30. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

31. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

32. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

33. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

34. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

35. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

36. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

37. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

38. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

39. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

40. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

41. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

42. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

43. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

44. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

45. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

46. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

47. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

48. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

49. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

50. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

51. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

52. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

53. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

54. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

55. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

56. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

57. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

58. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

59. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

60. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

61. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

62. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

63. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

64. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

65. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

66. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

67. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

68. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

69. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

70. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

71. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

72. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

73. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

74. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

75. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

76. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

77. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

78. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

79. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

80. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

81. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

82. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

83. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

84. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

85. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

86. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

87. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

88. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

89. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

90. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

91. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

92. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

93. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

94. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

95. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

96. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

97. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

98. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

99. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

100. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

101. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

102. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

103. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

104. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

105. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

106. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

107. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

108. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

109. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

110. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

111. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

112. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

113. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

114. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

115. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

116. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

117. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

118. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

119. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

120. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

121. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

122. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

123. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

124. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

125. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

126. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

127. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

128. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

129. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

130. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

131. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

132. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

133. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

134. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

135. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

136. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

137. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

138. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

139. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

140. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

141. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

142. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

143. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

144. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

145. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

146. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

147. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

148. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

149. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

150. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

151. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

152. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

153. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

154. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

155. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

156. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

157. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

158. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

159. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

160. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

161. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

162. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

163. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

164. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

165. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

166. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

167. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

168. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

169. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

170. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

171. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

172. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

173. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

174. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

175. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

176. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

177. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

178. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

179. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

180. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

181. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

182. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

183. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

184. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

185. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

186. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

187. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

188. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

189. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

190. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

191. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

192. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

193. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

194. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

195. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

196. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

197. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

198. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

199. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

200. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

201. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

202. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

203. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

204. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

205. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

206. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

207. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

208. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

209. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

210. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

211. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

212. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

213. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

214. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

215. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

216. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

217. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

218. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

219. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

220. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

221. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

222. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

223. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

224. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

225. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

226. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

227. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

228. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

229. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

230. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

231. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

232. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

233. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

234. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

235. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

236. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

237. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

238. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

239. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

240. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

241. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

242. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

243. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

244. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

245. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

246. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

247. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

248. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

249. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

250. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

251. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

252. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

253. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

254. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

255. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

256. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

257. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

258. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

259. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

260. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

261. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

262. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

263. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

264. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

265. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

266. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

267. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

268. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

269. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

270. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

271. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

272. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

273. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

274. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

275. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

276. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

277. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

278. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

279. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

280. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

281. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

282. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

283. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

284. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

285. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

286. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

287. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

288. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

289. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

290. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

291. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

292. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

293. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

294. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

295. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

296. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

297. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

298. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

299. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

300. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

301. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

302. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

303. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

304. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

305. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

306. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

307. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

308. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

309. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

310. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

311. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

312. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

313. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

314. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

315. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

316. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

317. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

318. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

319. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

320. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

321. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

322. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

323. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

324. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

325. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

326. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

327. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

328. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

329. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

330. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

331. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

332. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

333. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

334. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

335. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

336. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

337. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

338. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

339. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

340. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

341. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

342. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

343. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

344. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

345. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

346. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

347. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

348. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

349. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

350. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

351. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

352. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

353. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

354. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

355. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

356. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

357. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

358. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

359. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

360. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

361. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

362. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

363. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

364. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

365. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

366. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

367. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

368. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

369. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

370. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

371. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

372. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

373. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

374. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

375. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

376. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

377. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

378. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

379. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

380. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

381. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

382. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

383. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

384. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

385. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

386. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

387. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

388. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

389. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

390. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

391. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

392. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

393. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

394. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

395. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

396. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

397. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

398. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

399. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

400. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

401. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

402. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

403. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

404. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

405. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

406. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

407. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

408. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

409. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

410. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

411. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

412. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

413. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

414. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

415. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

416. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

417. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

418. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

419. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

420. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

421. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

422. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

423. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

424. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

425. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

426. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

427. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

428. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

429. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

430. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

431. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

432. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

433. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

434. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

435. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

436. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

437. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

438. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

439. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

440. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

441. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

442. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

443. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

444. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

445. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

446. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

447. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

448. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

449. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

450. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

451. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

452. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

453. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

454. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

455. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

456. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

457. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

458. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

459. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

460. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

461. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

462. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

463. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

464. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

465. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

466. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

467. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

468. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

469. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

470. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

471. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

472. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

473. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

474. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

475. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

476. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

477. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

478. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

479. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

480. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

481. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

482. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

483. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

484. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

485. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

486. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

487. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

488. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

489. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

490. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

491. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

492. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

493. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

494. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

495. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

496. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

497. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

498. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

499. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

500. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

501. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

502. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

503. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

504. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

505. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

506. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

507. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

508. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

509. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

510. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

511. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

512. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

513. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

514. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

515. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

516. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

517. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

518. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

519. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

520. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

521. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

522. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

523. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

524. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

525. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

526. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

527. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

528. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

529. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

530. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

531. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

532. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

533. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

534. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

535. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

536. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

537. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

538. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

539. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

540. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

541. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

542. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

543. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

544. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

545. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

546. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

547. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

548. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

549. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

550. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

551. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

552. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

553. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

554. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

555. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

556. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

557. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

558. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

559. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

560. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

561. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

562. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

563. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

564. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

565. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

566. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

567. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

568. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

569. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

570. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

571. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

572. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

573. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

574. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

575. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

576. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

577. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

578. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

579. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

580. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

581. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

582. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

583. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

584. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

585. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

586. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

587. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

588. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

589. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

590. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

591. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

592. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

593. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

594. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

595. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

596. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

597. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

598. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

599. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

600. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

601. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

602. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

603. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

604. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

605. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

606. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

607. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

608. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

609. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

610. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

611. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

612. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

613. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

614. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

615. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

616. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

617. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

618. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

619. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

620. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

621. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

622. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

623. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

624. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

625. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

626. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

627. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

628. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

629. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

630. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

631. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

632. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

633. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

634. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

635. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

636. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

637. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

638. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

639. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

640. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

641. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

642. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

643. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

644. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

645. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

646. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

647. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

648. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

649. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

650. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

651. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

652. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

653. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

654. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

655. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

656. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

657. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

658. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

659. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

660. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

661. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

662. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

663. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

664. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

665. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

666. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

667. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

668. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

669. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

670. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

671. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

672. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

673. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

674. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

675. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

Additional Terms and Conditions (ATC)

1. The bidder shall furnish Manufacturer's Authorization Form (MAF) from the OEM (Havells / Legrand / Schneider) for all switchgear items offered, specific to this bid.
2. The bidder must possess a valid ISO 9001:2015 certificate on the date of bid opening.
3. The bidder shall possess a valid Electrical Contractor Licence (Class A) issued by the Electrical Inspectorate of the State.
4. The successful bidder shall submit as-built drawings and test certificates before final payment.
5. Material shall be supplied only from the approved makes listed in Annexure-III.

101. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

102. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

103. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

104. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

105. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

106. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

107. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

108. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

109. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

110. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

111. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

112. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

113. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

114. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

115. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

116. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

117. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

118. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

119. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

120. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

121. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

122. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

123. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

124. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

125. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

126. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

127. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

128. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

129. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

130. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

131. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

132. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

133. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

134. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

135. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

136. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

137. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

138. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

139. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

140. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

141. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

142. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

143. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

144. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

145. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

146. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

147. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

148. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

149. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

150. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

151. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

152. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

153. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

154. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

155. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

156. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

157. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

158. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

159. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

160. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

161. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

162. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

163. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

164. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

165. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

166. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

167. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

168. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

169. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

170. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

171. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

172. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

173. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

174. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

175. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

176. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

177. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

178. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

179. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

180. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

181. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

182. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

183. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

184. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

185. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

186. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

187. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

188. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

189. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

190. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

191. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

192. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

193. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

194. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

195. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

196. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

197. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

198. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

199. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

200. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

201. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

202. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

203. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

204. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

205. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

206. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

207. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

208. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

209. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

210. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

211. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

212. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

213. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

214. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

215. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

216. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

217. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

218. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

219. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

220. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

221. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

222. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

223. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

224. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

225. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

226. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

227. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

228. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

229. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

230. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

231. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

232. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

233. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

234. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

235. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

236. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

237. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

238. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

239. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

240. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

241. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

242. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

243. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

244. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

245. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

246. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

247. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

248. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

249. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

250. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

251. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

252. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

253. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

254. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

255. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

256. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

257. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

258. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

259. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

260. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

261. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

262. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

263. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

264. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

265. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

266. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

267. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

268. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

269. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

270. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

271. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

272. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

273. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

274. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

275. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

276. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

277. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

278. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

279. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

280. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

281. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

282. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

283. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

284. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

285. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

286. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

287. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

288. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

289. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

290. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

291. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

292. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

293. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

294. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

295. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

296. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

297. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

298. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

299. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

300. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

301. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

302. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

303. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

304. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

305. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

306. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

307. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

308. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

309. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

310. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

311. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

312. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

313. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

314. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

315. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

316. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

317. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

318. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

319. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

320. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

321. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

322. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

323. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

324. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

325. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

326. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

327. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

328. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

329. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

330. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

331. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

332. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

333. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

334. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

335. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

336. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

337. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

338. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

339. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

340. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

341. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

342. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

343. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

344. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

345. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

346. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

347. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

348. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

349. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

350. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

351. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

352. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

353. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

354. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

355. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

356. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

357. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

358. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

359. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

360. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

361. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

362. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

363. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

364. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

365. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

366. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

367. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

368. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

369. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

370. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

371. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

372. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

373. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

374. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

375. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

376. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

377. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

378. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

379. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

380. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

381. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

382. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

383. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

384. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

385. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

386. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

387. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

388. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

389. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

390. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

391. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

392. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

393. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

394. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

395. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

396. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

397. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

398. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

399. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

400. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

401. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

402. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

403. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

404. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

405. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

406. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

407. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

408. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

409. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

410. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

411. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

412. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

413. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

414. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

415. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

416. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

417. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

418. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

419. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

420. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

421. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

422. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

423. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

424. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

425. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

426. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

427. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

428. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

429. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

430. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

431. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

432. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

433. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

434. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

435. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

436. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

437. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

438. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

439. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

440. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

441. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

442. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

443. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

444. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

445. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

446. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

447. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

448. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

449. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

450. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

451. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

452. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

453. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

454. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

455. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

456. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

457. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

458. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

459. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

460. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

461. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

462. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

463. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

464. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

465. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

466. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

467. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

468. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

469. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

470. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

471. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

472. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

473. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

474. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

475. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

476. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

477. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

478. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

479. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

480. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

481. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

482. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

483. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

484. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

485. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

486. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

487. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

488. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

489. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

490. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

491. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

492. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

493. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

494. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

495. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

496. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

Annexure-III: List of Approved Makes
MCB / RCCB / Distribution Boards: Havells, Legrand, Schneider
MCCB: Havells, Schneider, L&T
LT Cables and FRLS Wires: Polycab, Havells, KEI
LED Luminaires: Havells, Philips
Conduits and accessories: Polycab, Precision, AKG
Any item of a make not listed above shall be rejected.

Installation Guidelines (continued)

601. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

602. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

603. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

604. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

605. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

606. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

607. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

608. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

609. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

Installation Guidelines (continued)

610. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

611. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

612. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

613. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

614. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

615. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

616. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

617. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

618. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

619. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

620. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

621. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

622. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

623. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

624. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

625. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

626. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

627. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

628. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

629. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

630. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

631. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

632. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

633. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

634. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

635. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

636. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

637. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

638. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

639. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

640. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

641. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

642. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

643. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

644. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

645. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

646. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

647. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

648. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

649. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

650. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

651. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

652. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

653. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

654. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

655. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

656. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

657. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

658. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

659. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

660. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

661. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

662. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

663. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

664. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

665. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

666. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

667. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

668. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

669. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

670. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

671. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

672. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

Bill of Quantities (BOQ)

S.No.	Item Description	Unit	Quantity
1	Supply, installation, testing and commissioning of MCB 6A SP C-curve 10kA	Nos	120
2	Supply, installation, testing and commissioning of MCB 16A SP C-curve 10kA	Nos	180
3	Supply, installation, testing and commissioning of MCB 32A SP C-curve 10kA	Nos	60
4	Supply, installation, testing and commissioning of MCB 32A DP C-curve 10kA	Nos	24
5	Supply, installation, testing and commissioning of MCB 63A FP C-curve 10kA	Nos	12

Bill of Quantities (BOQ) (continued)

S.No.	Item Description	Unit	Quantity
6	Supply, installation, testing and commissioning of RCCB 40A DP 30mA	Nos	30
7	Supply, installation, testing and commissioning of RCCB 63A FP 100mA	Nos	8
8	Supply, installation, testing and commissioning of MCB distribution board 8 way TPN double door	Nos	10
9	Supply, installation, testing and commissioning of MCB distribution board 12 way SPN double door	Nos	18
10	Supply, installation, testing and commissioning of MCCB 100A TP 36kA thermal magnetic release	Nos	4

Bill of Quantities (BOQ) (continued)

S.No.	Item Description	Unit	Quantity
11	Supply, installation, testing and commissioning of MCCB 250A TP 36kA thermal magnetic release	Nos	2
12	Supply, installation, testing and commissioning of MCCB 100A TP 50kA thermal magnetic release	Nos	2
13	Supply, installation, testing and commissioning of LED panel light 36W 2x2 ft recessed	Nos	140
14	Supply, installation, testing and commissioning of LED batten 20W 4 ft	Nos	220
15	Supply, installation, testing and commissioning of LT XLPE armoured aluminium cable 4 core 16 sq mm 1.1 kV	Mtr	600

Bill of Quantities (BOQ) (continued)
S.No. | Item Description | Unit | Quantity

16 | Supply, installation, testing and commissioning of LT XLPE armoured aluminium cable 4 core 25 sq mm 1.1 kV | Mtr | 450

17 | Supply, installation, testing and commissioning of LT XLPE armoured aluminium cable 3.5 core 95 sq mm 1.1 kV | Mtr | 180

18 | Supply, installation, testing and commissioning of LT XLPE armoured aluminium cable 3.5 core 185 sq mm 1.1 kV | Mtr | 120

19 | Supply, installation, testing and commissioning of FRLS PVC insulated copper wire 1.5 sq mm single core | Mtr | 6000

20 | Supply, installation, testing and commissioning of FRLS PVC insulated copper wire 2.5 sq mm single core | Mtr | 4500

Bill of Quantities (BOQ) (continued)
S.No. | Item Description | Unit | Quantity

21 | Supply, installation, testing and commissioning of FRLS PVC insulated copper wire 4 sq mm single core | Mtr | 2000

22 | Supply, installation, testing and commissioning of FRLS PVC insulated copper wire 6 sq mm single core | Mtr | 1200

23 | Supply, installation, testing and commissioning of PVC rigid conduit 25 mm medium gauge with accessories | Mtr | 3500

24 | Supply, installation, testing and commissioning of GI earthing strip 25x3 mm | Mtr | 400

25 | Supply, installation, testing and commissioning of Copper plate earth pit 600x600x3 mm with charcoal and salt complete | Nos | 6

Bill of Quantities (BOQ) (continued)
S.No. | Item Description | Unit | Quantity

26 | Supply, installation, testing and commissioning of Perforated GI cable tray 300 mm wide | Mtr | 150

27 | Supply, installation, testing and commissioning of Street light pole 9 m octagonal with LED fitting 90W | Nos | 12

28 | Supply, installation, testing and commissioning of LT armoured copper cable 4 core 6 sq mm 1.1 kV | Mtr | 250

Bidder's Undertaking and Declarations

1. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.
2. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.
3. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.
4. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.
5. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.
6. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

Bidder's Undertaking and Declarations

1. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.
2. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.
3. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.
4. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.
5. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.
6. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

Bidder's Undertaking and Declarations

1. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.
2. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.
3. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.
4. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.
5. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.
6. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

Bidder's Undertaking and Declarations

1. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.
2. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.
3. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.
4. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.
5. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.
6. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

Bidder's Undertaking and Declarations

1. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.
2. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.
3. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.
4. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.
5. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.
6. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.