NOTICE INVITING e-TENDER - SAMPLE FOR TESTING (made-up, not a real tender)
NIT No. 18/EE/ED-IV/2026-27
Name of Work: Electrical installation including LT panel, cabling and lighting for the new Academic Block, Government Polytechnic College, Kota.
Estimated Cost put to tender: Rs. 31,40,000
Period of Completion: 3 (Three) Months
Last date of submission of bids: 12-11-2026 up to 15:00 hrs

Eligibility Criteria

1. The bidder should have satisfactorily completed during the last seven years: three similar works each of value not less than Rs. 20.00 Lakh, or two similar works each of value not less than Rs. 30.00 Lakh, or one similar work of value not less than Rs. 40.00 Lakh.
2. Average annual financial turnover during the last 3 years ending 31st March 2026 should be at least Rs. 1.20 Crore.
3. The bidder must hold a valid ISO 14001 certificate (Environmental Management System) on the date of submission of bid.
4. The bidder must hold a valid Electrical Contractor Licence issued by the competent authority of the State Government.
5. Similar work shall mean electrical installation works including LT panels and cabling in a building.

Earnest Money Deposit
Earnest Money: Rs. 62,800 to be deposited online through the e-procurement portal.
No exemption from Earnest Money shall be granted to any category of bidder, including MSEs.
Relaxation in turnover and experience criteria shall not be available to any category of bidder.

General Conditions (continued)

1. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

2. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

3. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

4. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

5. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

6. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

7. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

8. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

9. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

10. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

11. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

12. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

13. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

14. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

15. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

16. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

17. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

18. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

General Conditions (continued)

19. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

20. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

21. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

22. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

23. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

24. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

25. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

26. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

27. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

28. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

29. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

30. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

31. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

32. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

33. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

34. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

35. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

36. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

37. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

38. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

39. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

40. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

41. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

42. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

43. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

44. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

45. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

46. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

47. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

48. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

49. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

50. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

51. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

52. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

53. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

54. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

55. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

56. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

57. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

58. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

59. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

60. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

61. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

62. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

63. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

64. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

65. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

66. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

67. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

68. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

69. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

70. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

71. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

72. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

73. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

74. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

75. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

76. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

77. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

78. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

79. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

80. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

81. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

82. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

83. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

84. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

85. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

86. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

87. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

88. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

89. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

90. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

91. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

92. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

93. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

94. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

95. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

96. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

97. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

98. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

99. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

100. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

101. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

102. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

103. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

104. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

105. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

106. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

107. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

108. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

109. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

110. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

111. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

112. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

113. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

114. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

115. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

116. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

117. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

118. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

119. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

120. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

121. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

122. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

123. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

124. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

125. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

126. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

127. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

128. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

129. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

130. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

131. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

132. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

133. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

134. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

135. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

136. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

137. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

138. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

139. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

140. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

141. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

142. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

143. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

144. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

145. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

146. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

147. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

148. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

149. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

150. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

151. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

152. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

153. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

154. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

155. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

156. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

157. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

158. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

159. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

160. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

161. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

162. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

163. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

164. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

165. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

166. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

167. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

168. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

169. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

170. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

171. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

172. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

173. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

174. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

175. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

176. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

177. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

178. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

179. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

180. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

Special Conditions

1. The LT panel shall be manufactured by an L&T authorised panel builder, and the bidder shall submit authorisation from L&T for the panel and MCCBs.
2. All cables shall be of Polycab or KEI make only.
3. Work shall be executed during non-working hours where required by the Principal.

Technical Specifications (continued)

1. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

2. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

3. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

4. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

5. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

6. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

7. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

8. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

9. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

10. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

11. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

12. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

13. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

14. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

15. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

16. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

17. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

18. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

19. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

20. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

21. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

22. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

23. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

24. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

25. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

26. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

27. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

28. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

29. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

30. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

31. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

32. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

33. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

34. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

35. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

36. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

37. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

38. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

39. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

40. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

41. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

42. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

43. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

44. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

45. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

46. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

47. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

48. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

49. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

50. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

51. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

52. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

53. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

54. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

55. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

56. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

57. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

58. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

59. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

60. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

61. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

62. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

63. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

64. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

65. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

66. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

67. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

68. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

69. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

70. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

71. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

72. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

73. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

74. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

75. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

76. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

77. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

78. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

79. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

80. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

81. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

82. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

83. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

84. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

85. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

86. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

87. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

88. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

89. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

90. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

91. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

92. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

93. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

94. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

95. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

96. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

97. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

98. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

99. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

Technical Specifications (continued)

100. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

101. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

102. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

103. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

104. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

105. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

106. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

107. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

108. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

109. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

110. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

111. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

112. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

113. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

114. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

115. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

116. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

117. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

118. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

119. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

120. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

121. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

122. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

123. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

124. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

125. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

126. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

127. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

128. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

129. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

130. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

131. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

132. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

133. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

134. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

135. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

136. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

137. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

138. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

139. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

140. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

141. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

142. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

143. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

144. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

145. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

146. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

147. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

148. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

149. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

150. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

151. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

152. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

153. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

154. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

155. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

156. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

157. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

158. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

159. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

160. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

161. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

162. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

163. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

164. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

165. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

166. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

167. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

168. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

169. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

170. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

171. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

172. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

173. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

174. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

175. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

176. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

177. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

178. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

179. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

180. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

181. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

182. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

183. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

184. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

185. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

186. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

187. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

188. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

189. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

190. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

191. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

192. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

193. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

194. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

195. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

196. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

197. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

198. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

199. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

200. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

201. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

202. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

203. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

204. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

205. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

206. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

207. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

208. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

209. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

210. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

211. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

212. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

213. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

214. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

215. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

216. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

217. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

218. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

219. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

220. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

221. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

222. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

223. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

224. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

225. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

226. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

227. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

228. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

229. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

230. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

231. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

232. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

233. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

234. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

235. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

236. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

237. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

238. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

239. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

240. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

241. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

242. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

243. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

244. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

245. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

246. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

247. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

248. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

249. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

250. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

251. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

252. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

253. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

254. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

255. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

256. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

257. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

258. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

259. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

260. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

261. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

262. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

263. LED luminaires shall conform to IS 10322, with power factor above 0.95, THD below 10%, and a minimum efficacy of 100 lumens per watt.

264. Earthing shall be carried out as per IS 3043 using copper plate or GI pipe electrodes with charcoal and salt, and earth resistance shall not exceed 1 ohm.

265. Miniature Circuit Breakers shall conform to IS/IEC 60898-1, with a breaking capacity not less than 10 kA, C-curve characteristics, and shall be DIN rail mounted.

266. Residual Current Circuit Breakers shall conform to IS 12640 (Part 1), with a sensitivity of 30 mA for final circuits and 100 mA for sub-main circuits.

267. Moulded Case Circuit Breakers shall conform to IS/IEC 60947-2, with thermal-magnetic release, rated service breaking capacity Ics = 100% Icu.

268. LT XLPE armoured cables shall conform to IS 7098 (Part 1), with aluminium conductors, 1.1 kV grade, galvanised steel strip armour and PVC outer sheath.

269. FRLS PVC insulated copper wires shall conform to IS 694, 1.1 kV grade, multi-strand, with flame retardant low smoke sheathing.

270. Distribution boards shall be double door, powder coated, with IP 42 protection, complete with busbar, neutral link and earth bar.

Schedule of Quantities (BOQ) with estimated rates

Item | Description | Unit | Qty | Rate (Rs.) | Amount (Rs.)

1 | Providing and fixing MCB 16A SP C-curve 10kA | Nos | 90 | 165.00 | 14850.00

2 | Providing and fixing MCB 32A DP C-curve 10kA | Nos | 20 | 470.00 | 9400.00

3 | Providing and fixing RCCB 40A DP 30mA | Nos | 14 | 1350.00 | 18900.00

4 | Providing and fixing MCB distribution board 12 way SPN double door | Nos | 9 | 1800.00 | 16200.00

5 | Providing and fixing MCCB 250A TP 36kA thermal magnetic release | Nos | 2 | 18500.00 | 37000.00

6 | Providing and fixing MCCB 100A TP 25kA thermal magnetic release | Nos | 3 | 7200.00 | 21600.00

7 | Providing and fixing LED panel light 36W 2x2 ft recessed | Nos | 85 | 2050.00 | 184250.00

8 | Providing and fixing LT XLPE armoured aluminium cable 3.5 core 95 sq mm 1.1 kV | Mtr | 140 | 520.00 | 72800.00

Schedule of Quantities (BOQ) (continued)

9 | Providing and fixing LT XLPE armoured aluminium cable 4 core 25 sq mm 1.1 kV | Mtr | 320 | 190.00 | 60800.00

10 | Providing and fixing FRLS PVC insulated copper wire 2.5 sq mm single core | Mtr | 3800 | 22.00 | 83600.00

11 | Providing and fixing FRLS PVC insulated copper wire 4 sq mm single core | Mtr | 1500 | 35.00 | 52500.00

12 | Providing and fixing PVC rigid conduit 25 mm medium gauge | Mtr | 2400 | 38.00 | 91200.00

13 | Providing and fixing GI earthing strip 25x3 mm | Mtr | 250 | 85.00 | 21250.00

14 | Providing and fixing Cubicle type LT panel 400A with ACB incomer | Set | 1 | 385000.00 | 385000.00

501. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

502. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

503. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

504. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

505. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

506. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

507. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

508. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

509. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

510. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

511. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

512. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

513. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

514. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

515. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

516. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

517. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

518. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

519. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

520. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

521. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

522. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

523. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

524. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

525. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

526. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

527. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

528. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

529. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

530. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

531. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

532. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

533. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

534. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

535. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

536. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

537. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

538. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

539. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

540. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

541. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

542. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

543. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

544. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

545. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

546. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

547. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

548. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

549. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

550. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

551. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

552. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

553. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

554. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

555. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

556. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

557. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

558. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

559. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

560. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

561. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

562. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.

563. The Engineer-in-Charge shall have full powers to reject any material or work that does not conform to the specifications, and the Contractor shall remove such material from site at his own cost.

564. Payment shall be made within 30 days of receipt of the bill duly certified by the Engineer-in-Charge, subject to deduction of statutory taxes at source.

565. The defect liability period shall be twelve months from the date of completion. Any defect noticed during this period shall be rectified by the Contractor free of cost.

566. Liquidated damages at the rate of 0.5% of the contract value per week of delay, subject to a maximum of 10%, shall be levied for delay attributable to the Contractor.

567. The Contractor shall provide all tools, tackles, testing instruments and skilled manpower required for installation, testing and commissioning.

568. Insulation resistance, earth resistance and continuity tests shall be carried out in the presence of the Engineer-in-Charge and results recorded.

569. The Contractor shall maintain a site order book and comply with instructions recorded therein within the time specified.

570. Disputes, if any, shall be settled by arbitration under the Arbitration and Conciliation Act, 1996, and the seat of arbitration shall be the city of the Buyer.

571. The Contractor shall comply with all applicable laws, statutory rules and regulations in force, including the Indian Electricity Rules and the Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations.

572. All materials shall be new, of the best quality, and shall conform to the latest relevant Indian Standard Specifications, with BIS marking wherever applicable.